

Road Name	Closest Address / Intersection	Direction of Work	GPS Coordinates	Linear Footage	Type of Work	Column1
County Road 1200 / Zeeland Ave	4006 County Road 1200, Lubbock, TX 79407 / 4225 County Road 1200, Lubbock, TX 79407 / 4612 County Road 1200, Lubbock, TX 79407	North-South	33.547668, -102.044 to 33.574382, -102.043955	10,264'	1,433 LF 48ct buried plowed, 258 LF directional bore in 1-1/4" HDPE, 50 LF driveway bore/dry bore, 715 LF 12ct aerial on new 6M strand, 4,801 LF 24ct aerial on new 6M strand, 2,663 LF 48ct aerial on new 6M strand, and 334 LF 144ct aerial on new 6M strand	
County Road 6900 / 50th St	County Road 1200 W & 50th St, Lubbock, TX 79407	East-West	33.548575, -102.045919 to 33.548552, -102.052770	3,381'	309 LF 48ct buried plowed, 95 LF directional bore in 1-1/4" HDPE, 175 LF 12ct aerial on new 6M strand, 2,729 LF 24ct aerial on new 6M strand, and 73 LF 48ct aerial on new 6M strand.	
County Road 6740	10210 County Road 6740, Lubbock, TX 79407 / 9912 County Road 6740, Lubbock, TX 79407	East-West	33.5721, -102.0373	1,074'	1,074 LF 12ct aerial on new 6M strand.	
County Road 6840	County Road 6840, Lubbock, TX 79407	East-West	33.555950, -102.043874 to 33.554992, -102.047309	43'	43 LF 48ct aerial on new 6M strand.	
46th St	46th St near County Road 1160 / Chaparral Dr, Lubbock, TX 79407	East-West	33.551880, -102.045015 to 33.551951, -102.045016	256'	121 LF 12ct buried plowed, 80 LF directional bore in 1-1/4" HDPE, and 55 LF 24ct aerial on new 6M strand.	
County Road 1160 / Chaparral Dr	4808 County Road 1160, Lubbock, TX 79407 / 5020 County Road 1160, Lubbock, TX 79407	North-South	33.548893, -102.048045 to 33.554180, -102.047306	412'	412 LF 12ct buried plowed.	
County Road 6870 / Creek 6870	County Road 6870, Lubbock, TX 79407	East-West	33.550579, -102.047255 to 33.550728, -102.047256	229'	169 LF 48ct buried plowed and 60 LF directional bore in 1-1/4" HDPE	
County Road 1150	4603 County Road 1150, Lubbock, TX 79407	East-West	33.549722, -102.049517 to 33.553277, -102.050517	1,443'	1,253 LF 12ct buried plowed, 130 LF directional bore in 1-1/4" HDPE, and 60 LF 12ct aerial on new 6M strand.	